

Temporary Cantilevered Landing Platforms

Temporary cantilevered steel landing platforms designed and fabricated.
Designed to facilitate largest equipment loads
Platforms attached and braced off the main steel structure
(shown red on photographs)



- A Safe and Efficient method of loading equipment and materials into the building.
- No scaffold at ground level to interfere with site movements and access.
- Costs offset by flexibility at ground level and no scaffold hire
- Platforms can be moved to new locations to suit build sequence (structure predrilled in advance)



Graham Hutchison – Jacobs – 0161 741 7904

DBP00014