



Temporary Laydown Platforms for Materials storage

Temporary lay down / fabrication area floors were established in the ' future' empty areas of a new Production Building. These Temporary floors were formed by moveable steel floor sections which were fabricated to suit standard bay sizes within the structural steelwork frame .

Floor sections approximately 1.2m wide strips could easily be relocated by small crane as work progresses. Client retained for use in future development works.



Benefits

- Improve availability of materials close to the workfaces improving construction efficiency.
- Use ranged from piping and electrical materials to scaffold storage.
- Useable floor storage area in advance of concrete slabs.
- Flexibility to change work area without waiting for material to be loaded into the building
- Benefit to Client for future maintenance / shut down work

Graham Hutchison – Jacobs – 0161 741 7904